

KANSAS



21-31-21E
★ 1/10/85

WELL COMPLETION REPORT AND DRILLER'S LOG

API No. 15 — 099 — 21,224
County Number


RECEIVED

S. 21 T. 31S R. 21 E W

Loc. NE, NE

County Labette

640 Acres
N



Locate well correctly

Elev.: Gr. 835

DF _____ KB _____

Operator Hickory Creek Oil Company
 Address P.O. Box 379, Parsons, Kansas 67357
 Well No. 1 Lease Name Barnes
 Footage Location 175 feet from (N) (X) line 1350 feet from (E) (W) line
 Principal Contractor Lamampco Drilling Geologist J. W. Ellison
 Spud Date 5-30-80 Date Completed 6-3-80 Total Depth 275' P.B.T.D.
 Directional Deviation _____ Oil and/or Gas Purchaser Eureka Crude Purchasing

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Socks	Type and percent additives
Surface	9"	7"	20 lbs	32	Portland	4	20# CaCl
Production	6½"	4½"	9 lbs	238	Portland A	28	Prem gel (1 sk)

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Socks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
JAN 25 1985	
State Geologist WICHITA BRANCH	

INITIAL PRODUCTION

Date of first production _____ Producing method (flowing, pumping, gas lift, etc.) _____

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold) _____ Producing interval(s) _____

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ... Hickory Creek Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Barnes Dry Hole

S 21 T 31 S R 21 E W NE, NE Plugged 12-9-81

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	2		
Clay	2	7		
Sand & Gravel	7	32		
Hard White Sand	32	34		
Grey Sand	34	38		
Sandy Shale	38	54		
Gray Shale	54	66		
Sandy Shale	66	77		
Shale	77	107		
Lime	107	108		
Shale Lime Streaks	108	128		
Hard Lime	128	130		
Shale	130	132		
Coal	132	136		
Grey Shale	136	140		
Oil Sand Oder	140	149		
Shaley Sand	149	153		
Sandy Oder	153	173		
Sand	173	184		
Lime & Shale Streak	184	210		
Shale, Sandy Lime Streaks	210	240		
Sand	240	254		
Sandy Shale	254	270		
Lime	270	271		
Shale	271	275		
T.D.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	Signature
	Title
	Date

91-21-912