

26-34-29W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- THE TEXAS CO.
Farm- H.G. Adams "B" O/A No. 1

SEC. 26 T. 34 R. 29W
C NW NW
660' E & 660' S of NW cor.

Total Depth. 6403' PB 4464'
Comm. 8-3-59 Comp. 9-10-59
Shot or Treated.
Contractor. Stickle Drlg. Co.
Issued. 12-12-59

County Meade

KANSAS /



Elevation. 2472' DF

Production. 42,000,000 CFG
Cal Opn Flo.

Figures Indicate Bottom of Formations.

CASING:

18" 49' w/cem
8 5/8" 1651' w/800 sx cem.
5 1/2" 4508 w/215 sx cem.

surface	0
sand, clay, shale	290
red bed, sand	370
red bed shells, shale	880
shale, shells	2160
shale, lime shells	2455
shale, lime	2660
sdylime, shale	3150
lime, shale	3330
chalky lime, shale	3620
lime, shale	3725
shale, lime	4065
shale, lime, stks	4390
shale, lime	4406
lime, shale	4510
lime	4777
lime, chert	4836
lime	4900
lime, chert	4932
lime	4968
lime, chert shale	4985
lime, cherty lime	5018
lime, chert	5038
lime, shale	5249
lime	5310
lime, shale	5558
shale, lime	5653
lime, shale	5710
shale, lime	5788
lime	5835
sand	5837
sand, shale	5857
lime	5933
lime, shale	5990
shale, chalky lime	6074
lime, shale	6239
lime	6400 RTD
lime	6403
Total Depth	
PB	4464

Ran Welex Radiation Guard Log.

TOPS: SCOUT	
Council Grove	3223
Heebner	4347
Toronto	4388
Lansing	4490
Marmaton	5226
Cherokee	5430
Atoka	5595
Morrow	5766
1st Morrow sand	5818
2nd Morrow sand	5832
Mississippi	5867
St. Geneveive	6186