

V W & B DRILLING CO.Box 7 N. Hwy. 169
CHERRYVALE, KS 67335

A. Manners Farm Well # 6

Loc. S $\frac{1}{2}$ NW $\frac{1}{4}$ 30 31S 21E
County : LabetteDrilled for Hickory Creek Oil Co.
Commenced Drilling 3-6-81
Completed Drilling 3-10-81Figures indicate the bottom
of the formation

1	Top Soil	1	9	Dk. Gray Shale	308
10	Gray Clay	11		Streak of Coal	308
4	Yellow Clay	15	2	Dk. Shale	310
35	Gray Shale	50	10	Sandstone	320
19	Limestone	69	15	Gray Shale	335
6	Blk. Shale	75	9	Lt. Gray Shale	344
1	Lt. Gray Shale	76	4	Sandy Gray Shale	348
14	Limestone	90	6	Sandstone	354
4	Blk. Shale	94	14	Dk. Gray Shale	368
4	Lt. Gray Shale	98	10	Lt. Gray Sandy Shale	378
30	Sandy Gray Shale	128	6	Sandstone	384
2	Sandstone	130	16	Gray Shale	400
25	Gray Shale	155		Streak of Coal	400
15	Silty Gray Shale	170	12	Lt. Gray Shale	412
14	Gray Shale	184	14	Gray Shale	426
3	Blk. Shale	187	6	Dk. Gray Shale	432
	Streak of Coal	187	6	Lt. Gray Shale	438
12	Gray Shale	199	15	Dk. Gray Shale	453
2	Limestone	201	14	Sandstone	467
1	Gray Shale	202	12	Sandy Gray Shale	479
5	Blk. Shale	207		Streak of Coal	479
7	Gray Shale	214	23	Dk. Gray Shale	502
10	Lt. Gray Shale	224	1	Coal	503
21	Gray Shale	235	15	Lt. Gray Shale	518
5	Dk. Gray Shale	240	22	Gray Shale	540
10	Lt. Gray Shale	250		Streak of Coal	540
5	Gray Shale	255	8	Gray Shale	548
17	Silty Lt. Gray Shale	272	48	Mississippi Chat	596
8	Sandstone	280		Bottom of hole	596
19	Gray Shale	299			

Hole Size 6 $\frac{1}{4}$ inch. 38 feet of 7 inch casing
set with 7 sacks of cement and 15 lbs. calcium
chloride.

(316) 336-2171