


C. L. SEIBEL ET AL  
 Jones No. 1.

SEC. 26 T. 28 R. 14 E  
 NWc NW

Total Depth. 1191'  
 Comm. 11-1-43 Comp. 11-17-43  
 Shot or Treated.  
 Contractor. Lewis E. Taylor & Sons  
 Issued. 12-4-43

County. Wilson



CASING:

10" 27' P  
 8" 630' P  
 6 1/4" 1070' P

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

soil	2
clay	20
shale	35
lime	70
shale	170
lime	200
shale	203
lime	210
shale	222
wtr to drill w/at 236	
lime	263
shale	268
lime	278
shale	285
more wtr at 290	
sand	310
shale	322
lime	327
shale	350
lime HFW 435	468
shale	470
lime	481
sand	495
shale	512
lime	520
shale	528
lime gas at 533	533
shale	536
lime	615
shale	652
lime	658
shale	670
lime	676
shale	688
lime	695
shale	697
sand	700
shale	790
lime	821
shale	842
SIM 20' at 842	
lime	860
shale B.	865
lime	870
shale	885
sand	902
shale D.	953
shale L.	967
shale D.	1028
shale L.	1070
shale L.	1092
shale D.	1161
Miss. lime(wtr 1189)	1191
Total Depth.	

1191  
 1070  
 1141

26-28-15E  
 Sec. 26 T. 28 R. 15 14E  
 Loc. 4 N. & 1 W. of Fredonia  
 County Wilson (KGS-DRL)

Company

Farm Jones

No. 1

Total Depth 1191'


Comm.

Comp. Oct. 1943

Shot or Treated

Contractor

Issued



Elevation

Production

Casing	
20 in.	10 in 27'
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16
	8" 630'
	6" 970'

Figures Indicate Bottom of Formation

soil	2
clay, run 27' 10" csg.	20
shale	35
lime	70
shale	170
lime	200
shale	203
lime	210
shale, water to drill with at 236	222
lime	263
shale	268
lime	278
shale, more w. at 290'	285
sand	310
shale, H.F.W. @ 435'	322
lime	327
shale	359
lime	468
shale	470
lime	481
sand	495
shale	512
lime	520
shale	528
lime, gas	533
D. shale	536
lime	615
D. shale	652
lime	658
shale	670
lime	676
shale	685
shale	688
lime	695
shale	697

sand	700
shale	790
lime	821
shale, S.L.M. 20' @ 842'	842
lime	860
B. shale	865
lime	870
shale	885
sand	902
shale D.	953
L. shale, S.L.M.	967
D. shale	1028
L. shale	1070
L. shale	1092
D. shale	1161
Miss. lime, water 11791191	11791191

Orville Milliron - Jack Cook  
 Pete Mannen - Mack  
 Lewis Taylor - K. Nelson