

TALBOTT AND HUNTER.
Fee No. 1.

SEC. 29 T. 28 R. 12E.
SE NE NE SE
400' S 200' W NEo SE


Total Depth. 1138
Comm. 6-30-37 Comp. 10-2-37
Shot or Treated.
Contractor.
Issued. 11-13-37

County, Elk.

*(#2 Douglas
on Drilling App.)*

CASING.

12 $\frac{1}{2}$ " 16'
10" 347'
8" 833'



Elevation.

Production. 15 B.O.
20 BW.

Figures Indicate Bottom of Formations.

soil and clay	8
shale	18
lime	22
shale	40
red rock	50
shale	70
red rock	78
sdv shale	90
sand	110
shale	160
lime	175
shale	178
lime	179
shale	185
red rock	238
lime	246
shale	251
lime	254
shale	260
red rock	276
shale	280
red rock	290
sand	339
water 316	
shale	415
lime	433
shale	595
lime	675
little water 600	
sand	687
HFW 680	
lime	738
shale	832
show oil 832-840	
lime	894
shale	912
lime	922
shale	926
lime	932
shale	952
lime	1085
shale	1092
lime	1096
sdv lime	1115
shale	1122
lime	1133
sdv lime	1138

Total Depth.