

UNION NATIONAL BANK BLDG, WICHITA, KANSAS

Location SE cor SE/4 NW/4


Sec. 34 T.25 R.13E

Casing Record

County-Greenwood.

20" 10" 603 Farm- Geise No. 1
 15 1/8" 8 1/4" 858 Company- McCulloch Oil Co.
 12 1/2" 65/8" Contr.-
 12 1/2" 143 53/16" Comm.- 5/4/28. Comp.- 5/19/28.

Total Depth 1517'. Shots Quarts Between
 Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
 Date Issued, 6/9/28.

Elevation
 Initial Production Dry.

Formation	Depth
soil	15
sandstone	20
blue shale	50
sand Little water	130
shale	140
lime	142
shale	146
lime	148
slate	150
lime	153
slate	190
lime	196
slate	315
lime	320
lime hrd	335
lime	455
slate	530
lime	535
slate	540
lime HPW at 560'	598
slate	610
lime	615
slate	645
lime	665
pink lime	675
lime	725
shale	735
big lime	810
slate	840
sandy formation	850
white slate	940
Oswego lime	950
slate	975
lime	990
slate	1020
lime	1030
slate	1055
lime hrd	1090
slate	1095
lime	1130
slate	1135
lime	1140
black & blue slate	1385
slate bad cave	1420
black shale	1468
sand brkn	1474
sandy lime	1485
3 BW PH	
sand	1500
6 BW PH	
Hole filled up with sulphur water	1517
Total Depth	1517'