


I. M. FOSTER.  
 Trimm No. 1.

SEC. 36 T. 25 R. 13E  
 SE NW NE

Total Depth. 1515'  
 Comm. 4-2-36 Comp. 5-27-36  
 Shot or Treated.  
 Contractor.  
 Issued. 8-8-36.

County. Woodson



CASING.  
 10" 90'  
 8" 625'  
 6 5/8" 1062'  
 4 7/8" 1420'

Elevation.

Production. Dry.

Figures Indicate Bottom of Formations.

shell rock	5	lime	1062
clay	25	shale	1094
shale	140	lime	1097
lime	157	shale	1105
shale	303	shale	1119
lime	311	lime	1125
shale	314	shale	1127
lime	334	lime	1144
shale	348	shale	1148
lime	423	lime	1154
shale	426	shale	1229
lime	445	lime	1238
shale	448	shale	1268
lime	520	shale	1498
shale	541	lime	1502
lime	598	lime	1504
shale	602	sand	1510
lime	607	shale	1515
sand Oil	612	Total Depth	
sand water	618		
lime	621		
shale	636		
red rock	638		
shale	656	Sandy shale carried oil	1416-1502
lime	741		
shale	744		
lime	765		
ohat	775		
shale	783		
lime	812		
shale	960		
lime	965		
shale	985		
lime	997		
shale	1044		
sand	1059		