

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas

7-16-13w Plotted
g.e.f.

IND. TERR. ILL. OIL CO.
A. Hoffman No. 2-B.


SEC. 7 T. 16 R. 13W
SWc NW
330' N SL 330' E WL NW $\frac{1}{4}$

Total Depth. 3361'
Comm. 9-7-38 Comp. 9-30-38
Shot or Treated. 2000 Gals.
Contractor. Glenn Drlg. Co.
Issued. 1-7-39

JAN 7 1939

County. Barton

Rotary & Cable



Elevation.

CASING:
10 $\frac{3}{4}$ " 625'
7 " 3338'

Production. Pot. 1496 B.

Figures Indicate Bottom of Formations.

cellar	8	shale blue sft	2725
clay yellow sft	35	lime grey hrd	2775
shale & shells blue sft	242	shale grey, blue sft	2806
shale & lime shells, shale		lime wh hrd	2821
blue sft; lime shells wh		lime brown & grey hrd	2856
sft	512	brkn lime grey & blue med	2916
water sand, grey-wh sft	565	brkn lime grey med & shale	
shale blue sft	575	blue med	2967
shale & shells grey sft	595	lime grey & brown med hrd	3015
red bed red med	625	lime grey hrd	3052
red bed shale, red & blue sft	880	lime wh hrd	3073
anhydrite med	910	lime grey-wh med-hrd	3130
shale & shells blue sft	975	lime porous wh sft	3145
shale blue-grey sft & lime		lime wh-med-hrd	3154
shells wh sft	1245	lime wh hrd	3195
salt wh sft	1400	lime porous grey sft	3203
shale blk & blue sft	1555	Core lime porous grey sft	3207
anhydrite grey med	1570	Core lime wh hrd	3216
shale blk sft	1575	lime wh hrd	3256
shale blue sft	1580	lime grey hrd	3284
lime grey hrd	1630	Core lime dense grey hrd &	
lime wh med	1652	shale blue hrd	3296
anhydrite wh hrd	1680	lime grey med-hrd	3336
shale blue & med & shells		lime grey med	3339
white med	1726	Arbuckle lime grey med	3340
lime brown med	1760	dolomite brown sft	3345
shale & shells grey med	1790	Arbuckle lime brown hrd	3356 $\frac{1}{2}$
lime grey hrd	1813	lime dolomitic brown sft	3361
lime grey med	1895	Total Depth.	
lime grey med-hrd	1907		
shale pale blue rough	1928		
lime brkn grey med-hrd	2020		
shale blue sft	2054		
lime brown med	2075		
brkn lime & shale blk &			
grey med	2105		
brkn lime wh med & shale			
blue med	2161		
lime grey & wh hrd	2213		
lime grey hrd	2235		
shale sticky blue sft	2245		
brkn lime blue & wh med	2256		
brkn lime wh med & shale			
blue med	2339		
lime grey	2350		
shale blue & grey med	2370		
lime grey med	2422		
shale blue sft	2448		
lime grey hrd	2472		
shale blue sft	2527		
lime wh med-hrd	2542		
lime brkn & honeycomb			
white sft	2555		
lime grey med	2558		
lime grey hrd	2601		
lime brown hrd	2612		
lime wh med	2622		
shale blue med	2630		
brkn lime & shale blue med	2636		
lime grey med	2709		