

PLOTTED
G.E.J.
7-16-13W


SINCLAIR PRAIRIE OIL CO.
Louis Hoffman No. 2.

SEC. 7 T. 16 R. 13W
CEL NE
1320' fr N 330' fr EL NE $\frac{1}{4}$

Total Depth. 3371 $\frac{1}{2}$ '
Comm. 4-13-38 Comp. 5-6-38
Shot or Treated. 2000 Gals.
Contractor. Harbar Drlg. Co.
Issued. 7-23-38

County. Barton

JUL 23 1938



CASING:

13" 163'
7" 3364'
3" tbg 3368

Elevation.

Production. Pot. 1274 B.
No wtr.

Figures Indicate Bottom of Formations.

clay & sand rock	35
sand rock	45
sand shells	175
shale & shells	270
red bed	485
shale & shells	1125
salt	1160
shale & shells	1340
shale	1530
shale & shells	1620
shale & lime	1665
shale & shells	1875
shale & lime	1930
shale	1945
lime	1970
shale & lime shells	1995
shale & lime	2040
brkn lime	2096
lime	2220
shale	2235
lime	2265
shale & brkn lime	2340
shale & lime	2570
shale	2580
shale & lime	2700
shale	2730
lime	3095
brkn lime	3105
shale	3120
lime	3155
shale	3165
lime Arbuckle	3371 $\frac{1}{2}$
Total Depth.	

Fill up 1876' in 4 hrs.
Fill up 2520' in 8 hrs.
Swab 8 hrs made 281 bbls oil.