

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

Plot ed 98.
7-16-13W

SINCLAIR PRAIRIE OIL CO.
Louis Hoffman No. 7

SEC. 7 T. 16 R. 13W.
SE NW NE
990'fN 990'F W. lines NE $\frac{1}{4}$

County Barton.

Total Depth. 3364 $\frac{1}{2}$
Comm. 5-7-41 Comp. 5-22-41
Shot or Treated.
Contractor. Harbar Drilling Co.
Issued. 7-5-41

CASING.

13" 201'
85/8" 3393 $\frac{1}{2}$
2 $\frac{1}{2}$ " tubing.

Elevation.

Production. Pot. 31,189B.
no wtr. drawdown
Allowed Pot. 3000B.

Figures Indicate Bottom of Formations.

shale and shells	202	
shale	390	
shale and shells	646	Top of rotary table.
shale shells red bed	892	
anhydrite	940	
shale and shells	1345	
salt	1410	
shale and shells	1600	
shale chert and iron	1720	
shale and lime	1845	
lime	1885	
lime and shale	1965	
lime	2050	
lime and shale	2090	
shale and lime	2260	
lime	2320	
lime and shale	2395	
shale and lime	2465	
shale	2650	
shale and lime	2890	
lime	3053	
shale and lime	3074	
lime broken	3090	
line	3364 $\frac{1}{2}$	

Total Depth.

Top of Arbuckle 3358 $\frac{1}{2}$ - set 85/8" at 3360'8"
Meas. fr. derrick floor.

T.D. 3364 $\frac{1}{2}$ in Arbuckle.
Fill up 2150' in 2 hours.
no test before acid.
Acidized 1000 gal.
5-28-41 on test by draw down method
made an indicated pot. 31,189 bbls.
oil no water

Top Pot. Allowed for pool is 3000 B.

Surface level to bottom of cellar 4'
Surface level to derrick floor 3'5"
Derrick floor to top of rotary table 1'2"

