

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bk Bldg., Wichita, Kansas.


9.2 Jameson
8-16-13W

T. C. JOHNSON
Henry Bitter, Jr. No. 5.

SEC. 8 T. 16 R. 13W
Gen EL SW $\frac{1}{4}$

Total Depth. 3386 $\frac{1}{2}$ '
Comm. 1-22-38 Comp. 2-11-38
Shot or Treated. 5000 Gals.
Contractor. Mitchell Drlg. Co.
Issued. 3-26-38

County. Barton



MAR 28 1938

CASING:
10" 630'
7" 3378'

Elevation.

Production. Pot. 1120 B.

Figures Indicate Bottom of Formations.

shale & shells	630
red bed	755
shale & shells	905
anhydrite	945
shale	1179
shale & lime shells	1328
shale	1380
salt	1470
shale & shells	1589
shale	1671
shale & lime shells	1935
brkn lime	2021
lime	2160
shale & lime shells	2300
shale	2330
shale & lime shells	2455
shale	2545
shale & lime shells	2623
lime	2650
shale	2810
brkn lime	2820
shale	2836
lime	2891
lime & shale	2948
lime	3110
shale & lime shells	3141
lime	3181
lime & shale	3240
lime	3386 $\frac{1}{2}$
Total Depth.	

show of oil 3295-3299