


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. LARIO OIL & GAS CO.
Farm. Hangen No. 1

SEC. 5 T. 32 R. 1E
C SE SE

Total Depth. 4118'
Comm. 5-8-63 Comp. 5-24-63
Shot or Treated.
Contractor. White & Ellis Drilg.
Issued. 8-10-63

County Sumner
KANSAS



CASING:
8 5/8" 446' cem w/390 sx.

Elevation. 1270' RB

Production. Dry

Figures Indicate Bottom of Formations.

shale & lime shells	260
lime	350
Anhydrite	456
lime & shale streaks	530
shale & lime streaks	640
sand, shale & lime	710
lime & shale streaks	930
shale & lime streaks	1050
lime & shale	1230
shale & lime shale	1320
shale	1585
shale & lime strks.	1825
lime & shale	2054
lime	2200
lime & shale	2375
shale & lime strks.	2410
lime & shale	2500
shale	2619
lime	2621
sandy shale & sand	2650
shale & sand	2667
sand	2720
shale	2780
shale & sand	2810
shale	2948
lime Kansas City	3198
shale & lime strks.	3345
lime & shale strks.	3572
shale	3605
chert (Miss.)	3617
lime (Miss.)	4020
shale	4052
sand	4070
shale	4075
sand	4118 RTD
Total Depth	

TOPS:	
Topeka	1857
Heebner	2300
Douglas Sand	2340
Brown Lime	2617
Stalnaker	2662
Kansas City	2946
Base Kansas City	3194
Cleveland Sand	3240
Marmaton	3288
Cherokee	3432
Mississippian	3604
Kinderhook	3982
Chattanooga	4012
Simpson Sand	4052
Base Upper Simpson Sand	4068
Second Simpson Sand	4086
Base Second Simpson Sand	4096