


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 502 East Murdock, Wichita, Kansas

Company- LARIO OIL & GAS CO.
 Farm- Rusk "B" No. 1

SEC. 8 T. 32 R. 1E
 NE SW NE

Total Depth. 4200' PB 4110'
 Comm. 10-17-59 Comp. 11-11-59
 Shot or Treated.
 Contractor. Gearhart-Canaday Drilg. Co.
 Issued. 1-30-60

County Sumner
 KANSAS



CASING:

8 5/8" 452' cem. w/260 sx.
 5 1/2" 4146' cem. w/100 sx.

Elevation. 1256 RB

Production. 75 BOPD @ NW

Figures indicate Bottom of Formations.

soil & clay	35
lime, shells & shale	130
lime & shale	480
lime, shale stks.	700
lime & shale	1299
shale & shells	1545
lime	2165
lime & shale	2285
lime	2330
sand	2340
sand & shale	2375
lime & shale	2540
shale	2652
sand	2664
sand & shale	2750
shale	2945
lime	3195
shale & lime	3280
shale & lime stks.	3330
shale & lime	3405
shale w/lime stks.	3435
shale & lime	3575
lime	3811
lime w/shale stks.	3834
shale & lime	3937
shale & dolomite	3952
shale & lime	4009
core Simpson	4028
sand & shale	4088
lime	4200 RTD
PDTD	4110
Total Depth	

TOPS: GEOLOGICAL

White Cloud Sand Zone	1664
Topeka	1848
Heebner	2295
Douglas Sand	2331
Brown Lime	2612
Stalnaker Sand Zone	2646
Kansas City	2946
Base Kansas City	3192
Cleveland Sand Zone	3234
Marmaton	3286
Cherokee	3426
Chert Conglomerate	3565
Mississippian	3568
Kinderhook Dolomite	3926
Chattanooga	3973
Simpson Sand	4007
Base Upper Simpson Sand	4024
Arbuckle	4089

11-15-59 Perforated 4 per foot 4010-4020'.