

34-16-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SHIELDS OIL PRODUCERS
Farm- Jenisch No. 5

SEC. 34 T. 16 R. 12W
NW NE NE

Total Depth. 3341'
Comm. 11-17-58 Comp. 11-27-58
Shot or Treated.
Contractor. Shields Drig.
Issued. 1-31-59

County Barton
KANSAS



Elevation. 1892' RB

Production. 30 BOPD

CASING:

3 5/8" 313' cem w/200 sx.
5 1/2" 3335' cem w/75 sx.

Figures Indicate Bottom of Formations.

shale	313
shale & shells	495
red bed	770
Anhydrite	805
shale	1390
lime & shale strks	2892
lime	2951
lime w/shale	2985
shale	3051
lime w/shale	3100
lime	3140
lime w/shale	3190
lime	3337 RTD
lime	3341
Total Depth	

TOPS:

Topeka	2673
Heebner	2956
Toronto	2971
Brown Lime	3045
Lansing-Kansas City	3066
Arbuckle	3333

DST #1 3063-3100, tool op 1 h4. w/strong
blow thruout. gas to surface in 40 min.
Rec. 1065' gassy oil, FFP 325#. BHP
1014#/20 min.

DST #2 3122-3140, tool op 1 hr., gas to
surface in 5 min. Rec. 2760' gassy oil.
IFP 276#, FFP 617#, BHP 690#/20 min.