

35-16-12W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- TENNESSEE GAS TRANSMISSION COMPANY
Farm- Lydia Harzman No. 1

SEC. 35 T. 16 R. 12W
SE SE NE

Total Depth. 3435'
Comm. 3-15-57 Comp. 3-24-57
Shot or Treated.
Contractor. Lewis Drilling Company
Issued. 4-27-57

County Barton KANSAS



Elevation. 1940' RB

CASING:

8 5/8" @270'

Production. Dry

Figures indicate Bottom of Formations.

surface soil & clay	40
shale	70
sand & shale	185
shale & Red Beds	385
sand	472
Anhydrite	490
Red Bed & shale	780
shale & lime	1925
lime	2085
sand	2100
lime	2295
shale & lime	2785
lime	3370
Conglomerate	3417
Arbuckle lime	3435
Total Depth	

TOPS	
Topeka	2732
Heebner	3018
Toronto (Scout)	3029
Douglas	3046
Kansas City	3128
Conglomerate	3368
Arbuckle	3416

DRILL STEM TESTS

DST #1 3032-3100'
1 hr. SI 20" Rec. 60'
wtry Mud. BHP 920
FFP-45

DST #2 3280-3320' 1 hr.
Rec. 15' mud. 20" BHP 300#.