

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
Union National Bank Bldg, Wichita, Kansas


FIELDS AND CROSS.
Mason No. 3.

SEC. 14 T. 25 R. 13E.
SE NE NW SW
1350' W. 600' S. Cen Sec.
County. Woodson.

Total Depth. 1491
Comm. 4-6-35 Comp. 4-17-35.
Shot or Treated. 90 qts 1454-77
Contractor.
Issued. 6-22-35

CASING.

10" 390' 65/8" 1433'
8 1/2" 1035'



Elevation.

Production. 30 bbls.,

Figures Indicate Bottom of Formations.

soil	3
lime	5
shale	35
lime	50
shale	90
sand	125
sdv shale	185
shale	390
lime	520
shale	650
lime	670
shale	698
lime	701
shale	712
lime	855
shale	980
lime	990
shale	1002
lime	1010
shale	1035
lime	1050
shale	1120
lime	1125
shale	1130
lime	1150
shale	1165
lime	1190
shale	1195
lime	1201
shale	1395
sdv shale	1400
shale	1447
sdv shale	1454
sand	1477
sdv shale	1485
shale	1491 Total Depth.

Water Record.

125' HW
760' 3 BW

First oil 1447'
Free oil 1454-77
Filled up 150' oil over night.
shot with 90 qts 1454-77
Filled up 400' oil
Pumped 30 bbls oil