

AS

PT

State Geological Survey

3-9-20E

WELL COMPLETION REPORT AND DRILLER'S LOG

WICHITA BRANCH

S. 3 T. 9S R. 20 E

Loc. SW/NE/NE

County Leavenworth

API No. 15 - 103 - 20095
County Number

Operator SAMSON OIL COMPANY

Address 842 One Energy Square, Dallas, Texas 75206

Well No. 5 Lease Name Wagner


Footage Location 990' feet from (N) (X) line 990' feet from (E) (W) line

Principal Contractor Berentz Drilling Company Geologist Bruce Reed

Spud Date 6/8/81 Date Completed 6/12/81 Total Depth 1540' P.B.T.D.

Directional Deviation none Oil and/or Gas Purchaser N/A

640 Acres N



Locate well correctly

Elev.: Gr. 1036'

DF KB 1043'

CASING RECORD

Report of all strings set - surface, intermediate, production, etc.

Table with 8 columns: Purpose of string, Size hole drilled, Size casing set (in O.D.), Weight lbs/ft., Setting depth, Type cement, Sacks, Type and percent additives. Row 1: Surface, 12-1/4", 8-5/8", 20#, 88' KB, Class H, 65, 3% CaCl.

LINER RECORD

PERFORATION RECORD

Tables for LINER RECORD (Top, Bottom, Sacks cement) and TUBING RECORD (Size, Setting depth, Packer set at).

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Table with 2 columns: Amount and kind of material used, Depth interval treated.

INITIAL PRODUCTION

Table for INITIAL PRODUCTION with fields for Date of first production, Producing method, Rate of production (Oil, Gas, Water), Gas-oil ratio, and Disposition of gas.

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209.

Operator
 SAMSON OIL COMPANY

DESIGNATE TYPE OF COMP.: OIL, GAS,
 DRY HOLE, SWDW, ETC.:
 Dry Hole

Well No. 5 Lease Name Wagner

S 3 T 9S R20 E
 XX

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0'	3'	Kansas City	558'(+483)
Shale & Lime	3'	90'	B/Kansas City	750'(+291)
Lime & Shale	90'	162'	Cherokee	950'(+91)
Shale & Shells	162'	429'	McLouth Sd	1466'(-425)
Lime & Shale	429'	563'	Mississippian	1510'(-469)
Lime KC	563'	754'	TD	1540'(-497)
Shale & Lime	754'	937'		
Shale	937'	1471'		
Sand, Shale stringers & coal	1471'	1472'		
Shale	1472'	1487'		
Miss. Lime	1487'	1540'		
RTD	1540'			
Core 1440' - 1486'				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Signature: *Donald D. Patterson*

Executive Vice-President

Title

June 23, 1981

Date

3-2-90E