

9-16-13W

# DRILLER'S WELL LOG

DATE COMMENCED: 05/06/81  
DATE COMPLETED: 05/12/81

Amber Oil Company  
MAES No. 2  
W/2 E/2 SW/4 SE/4  
Sec. 9, Twp. 16S, Rge. 13W  
Barton County, Kansas

ELEVATION: 1914' G.L.  
1919' K.B.

## FORMATION DATA:

869 - Anhydrite  
2815 - 3050' Lime  
3050 - 3070' Shale  
3070 - 3084' Lime  
3084 - 3132' Shale  
3132 - 3141' Lime, shale  
3141 - 3372' Lime  
3372 - 3379' Lime, shale  
3379 - 3387' Shale, lime, chert, sand  
3387' RTD

Anhydrite 869'  
Topeka 2815'  
Heebner 3050'  
Toronto 3070'  
Douglas 3084'  
B. Lime 3132'  
Lansing 3141'  
Base KC 3372'  
Conglomerate 3379'  
RTD 3387'

## SURFACE PIPE:

Ran 7 jts. new 20# 8-5/8" casing; tally 298.62' Set @ 305' w/ 185 sks 50/50 poz., 2% gel, 3% c.c., cement. circ., plug down @ 9:00 AM 5/7/81, by Howco

## PRODUCTION PIPE:

Ran 88 jts. new 4-1/2" csg., tally: 3390'; set @ 3386' w/ 175 sks 50/50 poz., 10% sa Plug down 11:27 P.M., 5/11/81 By

## A F F I D A V I T

STATE OF KANSAS )  
COUNTY OF BARTON ) ss.

Gary Christopher, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge and belief.