

10-16-13W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SOHIO PETRO. CO.
Farm - Ochs No. 1

SEC. 10 T. 16 R. 13 W
NEc NW

Total Depth. 3400'
Comm. 12-4-46 Comp. 12-15-46
Shot or Treated.
Contractor.
Issued. 1-25-47

County. Barton
KANSAS



Elevation. 1882 *sd*

CASING:
8" 275'

Production. Dry

Figures indicate Bottom of Formations.

cellar	0-4
post rock & shale	200
sand & shale	230
shale & shells	270
clay & shale	375
sand & iron	385
red rock & shale	475
shale & shells	840
anhydrite	870
shale & shells	1280
salt & shale	1510
lime & shale	1820
lime	1855
lime brkn	2000
lime & shale	2080
shale & shells	2710
lime	2845
lime & shale	2905
lime & dolomite	3368
conglomerate	3380
Arbuckle	3400
Total Depth.	

Tops:	
Anhydrite	838
Topeka	2788
Heebner	3018
Lansing	3098
Conglomerate	3366
Arbuckle	3378