

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


11-16-13W

Company- MORGENSTERN & SPECTER
Farm- Ehrlich No. 1

SEC. 11 T. 16 R. 13W
SW SW NW

Total Depth. 3308'
Comm. 4-2-59 Comp. 4-12-59
Shot or Treated.
Contractor. Triangle Drig.
Issued. 6-6-59

County Barton
KANSAS



CASING:

8 5/8" 251' cem w/175 sx.

Elevation. 1872' KB

Production. Dry

Figures Indicate Bottom of Formations.

surface clay	10
post rock	30
hrd gry shale & limestone	130
shale & shells	130
sandstone	195
shale & shells	205
hrd sandstone & pyrite	325
shale & shells	545
red bed	842
Anhydrite	872
shale & shells	1095
shale, shells & salt	1250
shale & shells	1605
limestone & shale	1630
limestone	1730
broken limestone	1855
limestone	1970
limestone & shale	2732
limestone	3038
shale	3086
limestone	3343
Conglomerate	3352
dolomite	3388 RTD
Total Depth	

TOPS:

Anhydrite	842
Topeka	2732
Heebner	3005
Toronto	3024
Brown Limestone	3086
Lansing	3100
Chert Conglomerate	3343
Arbuckle	3352