

State Geological Survey
WICHITA BRANCH

DRILLER'S WELL LOG

16-16-13W
file

DATE COMMENCED: 05/02/81
DATE COMPLETED: 05/06/81

Amber Oil Company
DEUTSCH No. 2
SW SE NE
Sec. 16, Twp. 16S, Rge 13W,
Barton County, Kansas

ELEVATION: 1920' G.L.
1925' K.B.

866 -	Anhydrite
2828 - 3063'	Lime
3063 - 3080'	Shale
3080 - 3093'	Lime
3093 - 3142'	Shale
3142 - 3152'	Lime, shale
3152 - 3398'	Lime
3398 - 3408'	Dolomite
3408'	RTD

FORMATION DATA:

Anhydrite	866'
Topeka	2828'
Heebner	3063'
Toronto	3080'
Douglas	3093'
B. Lime	3142'
Lansing	3152'
Arbuckle	3398'
RTD	3408'

SURFACE DATA:

Ran 8 jts. 20# new 8-5/8"
casing; tally: 337.65'
Set @ 344' w/200 sks 50/50
poz. 2% gel, 3% c.c. Cem.
circulated, plug down 8:50 PM
5/2/81, by Howco

PLUGGING DATA:

100 sks 50/50 poz. 2% gel,
3% c.c.:
50 sks @ 525'
30 sks @ 330'
10 sks & solid bridge @ 40'
10 sks in rathole
Compl. @ 10:30 AM 5/6/81
By Howco; Duane Rankin, plugger

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

RECEIVED
STATE CORPORATION COMMISSION

MAY 2 1981