


WELL LOG BUREAU — KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - CONTINENTAL OIL CO.
Farm - F.J.Schreiber No. 2.

SEC. 32 T. 16 R. 13 W
NW NE SE
3 30'S 990'W E $\frac{1}{2}$ Cor.

Total Depth. 3364'
Comm. 10-30-43 Comp. 11-20-43
Shot or Treated.
Contractor.
Issued. 3-4-44

County. Barton
KANSAS



CASING:
10 $\frac{3}{4}$ " 359' Cem.
6" 3345' Cem.

Elevation. _____

Production. Pot. 25 B. Min. Temp. Swbg

Figures Indicate Bottom of Formations.

surface soil	0-10
shale & shells	180
sand	220
red rock	225
sand	323
red bed	365
shale & shells	820
anhydrite	850
shells	860
shale & shells	1270
salt	1450
shale & shells	1625
shale	1635
lime	1835
lime brkn	1965
lime	2020
shale & lime	2100
shale	2180
shale & shells	2325
shale	2405
shale & shells	2720
lime	2743
shale	2795
shale & lime	2975
lime brkn	3085
lime sft	3118
lime	3364
Total Depth.	

Top Arbuckle Lime 3344

11-20-43 drld out cement
plug & hole filled 1200'
w/oil in 2 hrs
11-23-43 established a 25-bbl
minimum temporary swabbing
potential of oil by swabbing
90 bbls oil in 1 hr & 20 min.
Total Depth 3363 in Arb.Ls

Note: All above footages
calculated from cement flr
level, except formations.