

Company- SHAMROCK RECONDITIONERS
Farm- Omer Lynn No. 3

26 (KGS-DRL)
SEC. ~~25~~ T. 28 R. 15E
SE SW SE

Total Depth. 1610'

Cum. 6-29-57

Comp. 7-8-57


Strat. or Treated.

Contractor. Tee Drilling Co., Inc.

Installed. 5-28-60

County Wilson

KANSAS



Elevation. _____

Production. Dry

CASING:

8" 592'

7" 906'

Figures indicate Bottom of Formations.

lime	34
shale	144
lime	204
shale	280
lime	302
shale	317
lime	330
shale	352
lime	475 HFW (15 bailers per hr. at 375-380)
shale	484
lime	494
shale	505
lime	580
shale (black)	590
shale	654
lime	670
shells	690
shale	768
lime	772
shale	778
lime	855 HFW
sand	897 Gas
shale	949
sand (white)	959
shale	1007
sand	1016 Smell of oil
shale	1030
sand	1038
shale	1048
sand	1172 Gas at 1064, increase at 1146-show of free oil at 1146
chat	1224 Gas
lime	1275
Total Depth	

DRILLED FOR SHAMROCK RECONDITIONERS
April 19-59

well cleaned out to 1275'

lime & chert	1320
lime	1400
lime & shale st.	1475
lime	1500
shale	1508
Arbuckle	1610
Total Depth	