


WELL COMPLETION REPORT AND
DRILLER'S LOGAPI No. 15 — 009 — 21,880 ✓
County NumberS. 21 T. 16 R. 13 NE
W

Loc. NW NW SE

County Barton

640 Acres
N

Locate well correctly

Elev.: Gr.

DF KB 1961

Operator

Icer Addis

Address

Drawer 8038, Wichita, Kansas 67208

Well No.

1

Lease Name

Amerine

Footage Location

990

feet from (N) (S) line

990

feet from (E) (W) line

Principal Contractor

L. D. Drilling, Inc.

Geologist

Jim Musgrove

Spud Date

March 21, 1980

Date Completed

3-28-80

Total Depth

3467

P.B.T.D.

Directional Deviation

Oil and/or Gas Purchaser

N/A

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$ "	8-5/8"	28#	320'	60/40 Poxmix	200	2% gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	bbls.	MCF	bbls.	CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator ICER ADDIS		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:	
Well No. 1	Lease Name Amerine		DRY HOLE
S <u>21</u> T <u>16</u> R <u>13</u> ~~EX~~ W			
WELL LOG		SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME
Anhydrite			
Severy	2853'		
Topeka	2871'		
Heebner	3103'		
Toronto	3121'		
Douglas	3133'		
Brown Lime	3184'		
Lansing	3192'		
Conglomerate	3426'		
Arbuckle	3436'		
RTD	3467'		
D&A	3467'		
DST #1 - 3187'-3210' Tool Open 1 Hr. (45-30-45-30), Recovered 45' mud and 60' muddy water w/few oil specks ISIP - 860# psi FSIP 853 psi IFP - 48 psi FFP 66 psi DST #2 - 3322'=3380'- Tool Open 1Hr. (45-30-45-30), Rec. 20' mud with few oil specks on top of tool ISIP 721 psi FSIP 581 psi IFP 31 psi FFP 31 psi DST #3 - 3408-3444-, Open 1 Hr. (45-30-45-30), Recovered 10' sl. Oil cut mud. ISIP 787 psi FSIP 688 psi IFP 33 psi FFP 33 psi			
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.			
Date Received	 Icer Addis Owner April 9, 1980 Date Signature Title Date		