


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas

Company- K & P OIL CO.
 Farm- Popp No. 1

SEC. 21 T. 16 R. 13W
 C N/2 NE NE

Total Depth. 3413'
 Comm. 3-5-64 Comp. 3-14-64
 Shot or Treated.
 Contractor. Sholom Drilling Co., Inc.
 Issued. 9-19-64

County Barton
 KANSAS



Elevation. 1941' KB

Production. 20 BO / 340 BWPD

CASING:
 8 5/8" 334' cem w/225 sx.
 5 1/2" 3409' cem w/150 sx.

Figures Indicate Bottom of Formations.

surface clay	30
post rock	90
shale & sand	265
wtr. sand	305
shale & redbeds	334
shale & sand	595
redbed	883
Anhydrite	912
shale & shells	1670
shale & lime	2010
lime	2090
lime & shale	2855
lime	3080
shale	3084
lime	3109
shale	3160
lime	3167
lime	3413
Total Depth	

TOPS: LOG

Anhydrite (sample)	883
Topeka	2813
Heebner	3084
Toronto	3102
Douglas	3114
Brown Lime	3165
Lansing	3173
Base Kansas City	3390
Arbuckle	3408

DST 3164-3242' 45' mud w/specks oil

DST 3398-3413' Rec. 1260' GSy oil-1 hr.
 BHP 1060-1060, FP 160-480