

21-16-13W

PZ

DRILLER'S WELL LOG

State Geological Survey
Geological Survey

DATE COMMENCED: 7-11-80
DATE COMPLETED: 7-15-80

Amber Oil Co.
Prusa B #2
NE SE NE Sec. 21-16-13 W
Barton County, KS

ELEVATIONS K.B.
G.L.

FORMATION DATA

875- 902'	Anhydrite
3068-3073'	Shale
3073-3084'	Lime
3084-3097'	Lime
3097-3148'	Shale
3148-3158'	Lime & Shale
3158-3387'	Lime
3387-3397'	Lime & Shale
3397-3411'	Shale, Lime, Chert & Sand
3411-3415'	Dolomite
3415'	RTD

Anhydrite	875
Heebner	3068'
Toronto	3084'
Douglas	3097'
Brown Lime	3148'
Kansas City	3158'
Base Kansas City	3387'
Conglomerate	3397'
Arbuckle	3411'
RTD	3415'

SURFACE PIPE:

Set @ 368' 8 5/8" 28#
used casing w/200 sks
50/50 Pozmix 2% Gel 3% c.c.
w

PLUGGING:

Mud to 480' w/50 sks
50/50 Pozmix
Mud to 300' w/30 sks
Mud to 40' w/1/2 sks hulls
Plug and 10 sks
5 sks in rat hole
7-15-80 1:15

RECEIVED
STATE CORPORATION COMMISSION
AUG 13 1980
CONSERVATION DIVISION
Michigan, Kansas

AFFIDAVIT

STATE OF KANSAS)
COUNTY OF BARTON) ss.

Larry Curtis, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.