

TYPE

AFFIDAVIT OF COMPLETION FORM

23-16-1300
ACO-1 WELL HISTORY
Compt. _____

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 6039 EXPIRATION DATE 6-30-84

OPERATOR L D Davis/L D Drilling, Inc.

API NO. 15-009-23,559

ADDRESS Rt #1, Box 183B

COUNTY Barton

Great Bend, KS 67530

FIELD Trapp

** CONTACT PERSON L D Davis

PROD. FORMATION Arbuckle

PHONE 316-793-3051

PURCHASER Koch Oil Company

LEASE KOELLER

ADDRESS Wichita, Kansas

WELL NO. 2

DRILLING CONTRACTOR L D Drilling, Inc.

WELL LOCATION SW SW SE

ADDRESS Rt #1, Box 183B

580 Ft. from South Line and

Great Bend, KS 67530

2230 Ft. from East Line of

the SE (Qtr.) SEC 23 TWP 16 RGE 13 W

PLUGGING

CONTRACTOR

ADDRESS

WELL PLAT

(Office
Use Only)

KCC

KGS ☒

SWD/REP

PLG.

TOTAL DEPTH 3419' Cable tools drilled 4' to 3923' PBTB

SPUD DATE 5-27-84 DATE COMPLETED 6-5-84

ELEV: GR 1952' DF _____ KB 1958' RE-KCE

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(CABLE)~~ TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE _____

Amount of surface pipe set and cemented 505' DV Tool Used? none

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil) Gas, Shut-in Gas, Dry, Disposal, Injection, Temporarily Abandoned, OWWO. Other _____

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

that: L. D. Davis, being of lawful age, hereby certifies

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

OPERATOR L D Davis/L D Drilling Inc LEASE KOELLER

SEC. 23 TWP. 16 RGE. 13 W

WEI - 21

FILE IN WELL INFORMATION AS REQUIRED:

WELL NO. 2

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.			Anhy	881-905
			Heebner	3072'
			Toronto	3090'
Post Rock	0	102	Douglas	3103'
Shale	102	280	Brown Lime	3156'
Red Bed	280	510	Lans K/C	3165'
Red Bed & Blue Shale	510	650	Base K/C	3384'
Red Bed	650	881	Arbuckle	3413'
Anhy	881	905		
Shale	905	1555		
Lime & Shale	1555	3419		
DST #1 3374 - 3419				
TIMES: 30-30-30-30				
BLOW: Weak Blow - Increasing slightly				
REC: 120' HOCM				
IFP: 17-34 FFP: 42-59 ISIP: 929 FSIP: 895				

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used				Depth interval treated	
OPEN HOLE COMPLETION					
Date of first production		Producing method (flowing, pumping, gas lift, etc.)		Gravity	
June 5, 1984		pumping			
Estimated production -I.P.	Oil	Gas	Water	Gas-oil ratio	
	20		20 %		
	bbls.	MCF	bbls.		CFPB
Disposition of gas (vented, used on lease or sold)			Perforations		

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{2}$ "	8-5/8"		505'	REG POZ	275	2% Gel, 3% CC
Production	7-7/8"	5 $\frac{1}{2}$ "		3416'	50/50 POZ	150	18% SS, 20 bbl Salt Flush, 5# Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Pecker set at			