KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU—KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CIRCLE OIL

FARM Christians NO. 2

SEC. 24 T. 16 R. 13W
LOC. SE NE SE

TOTAL DEPTH 3424'
COMM. 6-20-66 COMP. 6-25-66
SHOT OR TREATED
CONTRACTOR Sage Drilling
ISSUED 12-16-67

COUNTY Barton

KANSAS



CASING

20 10
15 8 5/8" 315' cem w/ 200 sx
12 6
13 5 " 3417' cem w/ 100 sx

ELEVATION 1946' KB

PRODUCTION 85 BOPD, NW GR 40 (Arb Oh 3417-24

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil	0	680
Red Bed	680	873
Anhydrite	873	901
Shale & Shells	901	1560
Shale & Lime	1560	2916
Lime	2916	3007
Lime & Shale	3007	3230
Lime	3230	3420
TOTAL DEPTH		3424

TOPS: SMP

Heebner	3068
Brown lime	3154
Lansing	3166
Base Kansas City	3397
Arbuckle	3414

5½" @ 3417' w/100 sax

I certify that this is a true and correct copy of the above log to the best of my knowledge.



SAGE DRILLING CO., INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 28th day of June, 1966.

Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1966.

LASMO Energy Corporation

KANSAS-OKLAHOMA REGIONAL OFFICE
P.O. Box 1365
Great Bend, Kansas 67530
Telephone: (316) 792-2585

January 27, 1986

Kelso Casing Pulling
Box 347
Chase, Kansas 67524

Darrell;

Please find below the information you will need to obtain the proper paperwork from the KCC to plug out the following wells. Please plug immediately.

Christians # 2 Injection
SE NE SE
Section 24-16S-13W
Barton County, Kansas
8-5/8" at 315' with 200sx. cement
5-1/2" at 3417' with 100 sx. cement
RTD= 3420' Deepened to 3428'
Plug Back TD= 3379'
Perforations 3320-26; 3305-10; 3202-06; 3172-76; 3250-60
Squeezed 750' with 260 sx. cement