

KANSAS GEOLOGICAL SOCIETY

Loc. NW SW NW

County Barton

640 Acres
N

Locate well correctly

Elev.: Gr. 1933

DF _____ KB 1938

API No. 15 — 009 — 20,768
County Number

Operator

J. S. Tomlinson

Address	1022 United Founders TWRS, Oklahoma City, Oklahoma
---------	---

Well No.	Lease Name
#1	Allen

Footage Location *NW/4*
 990 feet from (S) (S) line 330 feet from (W) (W) line

Principal Contractor RED TIGER	Geologist J. E. JESPERSEN
--	-------------------------------------

Spud Date 1-8-74	Total Depth 3410	P.B.T.D. 3410
---------------------	---------------------	------------------

Date Completed 3-15-74	Oil Purchaser PHILLIPS
---------------------------	---------------------------

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12 $\frac{1}{4}$ "	8 $\frac{5}{8}$	28 $\frac{1}{2}$	375'	REG.	200	2% GEL 3% CACI
PRODUCTION	7 $\frac{7}{8}$	5 $\frac{1}{2}$	14 $\frac{1}{2}$	3404'	POZ. A	150	18% SALT

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			OPEN HOLE		3404-10
Size 2 7/8	Setting depth 3406'	Packer set at NONE			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED
STATE
1914

INITIAL PRODUCTION

Date of first production 2-21-74		Producing method (flowing, pumping, gas lift, etc.) PUMPING	
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls.	Gas - 0 - MCF	Water 70 bbls.
Disposition of gas (vented, used on lease or sold)		Gas-oil ratio CFPB	
		Producing interval(s) 3404-10 ARBUCKLE	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

C-10-1972

Operator SID TOMLINSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name ALLEN	OIL
S 25 T 16 R 13 W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.


SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>DST #1- 3385-3405 (ARBUCKLE)</u> TOOL OPEN 1 HOUR. Rec 25' CLEAN OIL. ISIP 986 #/30" FSIP 881 #/30"	FP	19#-38#		
<u>DST #2 3401-3410 (ARBUCKLE)</u> TOOL OPEN 1 HOUR. Rec 120' GAS IN PIPE, 1700' FREE OIL, 800' muddy OIL, 50' WATER. FP 388# - 948# ISIP 1091 #/30" FSIP 1091 #/30"				
RAN DRESSER ATLAS GAMMA RAY / NEUTRON LOG				
LOG TOPS:			SAMPLE TOP	
SC	868' (-1070)			
HCEBNER	3056 (-1118)		ANHYDRITE	868'
TORONTO	3074 (-1136)			
BEN. Lm,	3144 (-1206)			
LANSING	3160 (-1222)			
ARBUCKLE	3401 (-1463)			
RTD	3410 (-1472)			

34567891011121314

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Sid Tomlinson
Signature
Operator
Title
4-11-74
Date