

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS



COMPANY **CIRCLE OIL, INC.**

SEC. 24 T. 16 R. 13W
 LOC. N/2 SE NE

FARM **Christians** NO. 7

TOTAL DEPTH **3407**
 COMM. **8-16-67** COMP. **8-23-67**
 SHOT OR TREATED
 CONTRACTOR **Sage Drlg.**
 ISSUED **11-11-67**

COUNTY **Barton**



CASING

20 10
 15 8 5/8" @ 353' w/200 SX
 12 6
 13 5

ELEVATION 1929' KB

PRODUCTION PMP 96 BOPD, NW
 ARB 3398-3407

FIGURES INDICATE BOTTOM OF FORMATIONS

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil	0	354	TOPS: SCOUT
Shale & Shells	354	525	Topoka 2771
Red Bed	525	858	Heebner 3048
Anhydrite	858	889	Toronto 3064
Shale & Shells	889	1526	Douglas 3076
Lime & Shale	1526	1775	Brown Lime 3134
Shale & Lime	1775	2044	Lansing 3147
Lime & Shale	2044	2285	B/Kansas City 3385
Shale & Lime	2285	2680	Arbuckle 3398
Lime & Shale	2680	2965	
Lime	2965	3035	
Lime & Shale	3035	3265	
Lime	3265	3392	
L & Shale	3392	3407	5 1/2" @ 3397' w/150 sax

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
 Lawrence F. Gray

Subscribed and sworn to before me this 29th day of August, 1967.

Louise F. Howard