

PLotted
G. E. Garrison

STANOLIND OIL & GAS CO.
M.P. Morrison No. 1-A

SEC. 27 T. 16 R. 13W.
SW SW SW
330' N of S.L. 330' E of W.L.


Total Depth. 3425
Comm. 9-19-37 Comp. 10-10-37
Shot or Treated.
Contractor.
Issued. 1-15-38

County Barton.

15
JAN 8 1938

CASING.

103/4" 240'3"
6" 3417'9"



Elevation.

Production. DRY.

Figures Indicate Bottom of Formations.

lime shells and shale	171
sand shells and shale	350
sand shale and shells	615
red bed shale and shells	795
shale sand and red bed	1050
shale and shells	1395
shale salt and shells	1530
shale and lime	1625
lime and gyp	1685
lime	1775
broken lime and shale	1921
lime	1981
lime and shale	2851
lime	2935
lime and shale	3180
lime	3390
coring record - Rotary.	
shale blk	3392
lime and shale cong.	3393
lime grey with shale	
partings	3396
lime white to tan	3400 $\frac{1}{2}$
shale dark olive green	3401 $\frac{1}{2}$
shale red	3405
lime red	3408
shale red and green	3410
dolomite grey very shaley	
red and green no show	3413
Top siliceous	3410
dolomite tan some porosity	
no show of oil	3417
dolomite dense streaks	
of green shale	3420 $\frac{1}{2}$
dolomite very small show	
of oil	3421
dolomite brown spotted	
saturation	3423
dolomite sugary coarse	
solution cavities 50%	
saturation	3425
Total Depth.	

Siliceous lime 3410-3425