

27-16-13W

KANSAS GEOLOGICAL SOCIETY  
508 East Murdock  
Wichita, Kansas

OCT 11 1969

DRILLER'S LOG

COMPANY  
CONTRACTOR  
FARM  
LOCATION  
  
COMMENCED  
COMPLETED

Al Tipton  
LEBEN DRILLING, INC.  
SCHMIDT #1  
~~SW SE NW~~ SECTION 27-16S-13W  
BARTON COUNTY, KANSAS  
7-23-69  
7-31-69

S/2 S/2 NW

oil

0	332	Shale
332	830	Shell, Shale
830	874	Shale, Shells
874	894	Andhdrite
894	1270	Shale, Lime
1270	1590	Shale
1590	2195	Lime, Shale
2195	2350	Shale, Lime
2350	2745	Lime, Shale
2745	3355	Lime
3355	3422	Lime, Muck
	<u>3422</u>	<u>RTD</u>

8 5/8" 20# new surface casing set @ 332' cemented with 225 sacks Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Schmidt #1 Well, located SW SE NW Section 27, Township 16 South, Range 13 West, Barton County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite  
Leslie Kite

STATE OF KANSAS )  
                          ) SS  
COUNTY OF BARTON )

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of August, 1969,