

KANSAS

WELL COMPLETION REPORT AND
DRILLER'S LOGState Geological Survey
WICHITA BRANCHAPI No. 15 — 191 — 21,313
County Number

Operator

Holt Oil & Gas Corporation

Address

8150 N. Central Expwy., Suite 1255, Dallas, TX 75206

Well No.

#5

Lease Name

Evans

Footage Location

990 feet from (X) (S) line

1,650 feet from (E) (Y) line

Principal Contractor

Ramco Drilling Corporation

Geologist

Roger N. Planalp

Spud Date

8-27-81

Date Completed

9-19-81

Total Depth

3,707'

P.B.T.D.

Directional Deviation

1/2°


Oil and/or Gas Purchaser

Conoco, Inc.

S. 17 T. 32S R. 2 E

Loc. NE SW SE

County Sumner

640 Acres
N

Locate well correctly

Elev.: Gr. 1,230'

DF KB 1,241'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8-5/8"	23#	253'	Class "A"	200	3% CaCl, 2% gel
Production	7-7/8"	4 1/2"	9.5#	3,704'	50/50 Pozmix Class "A"	300	2% gel, 18% salt, 3/4% CFR-2, 5#/sx gilsonite

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at
2-3/8"	3,650"	

ACID, FRACTURE, SHOT, GEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)			
9-24-81	Pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	82 bbls.	MCF	0 bbls.	CFPB
Disposition of gas (vented, used on lease or sold)			Producing interval (s)	
Temporarily vented			3,704' - 3,707'	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

WELL LOG

State Geological Survey
WICHITA BRANCH
SEP
17-32-2EP1

WELL NAME: Evans #5

OPERATOR: Holt Oil & Gas corp.

SPUD DATE: 8-26-81

CONTRACTOR: Ramco Drilling Company

COMPLETION DATE: 9-3-81

CASING: 8 5/8 23# new, Set @ 253' w/200
sx Class H, 3% cc

LOCATION: NE SW SE
Sec. 17-32S-2E

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface	0	890
Shale and Lime	890	2788
K. C. L.	2798	2937
Lime	2937	3694
Simpson Sand & Arbeckle	3694	3712
RTD	3712	

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1981

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

COUNTY OF SEDGWICK