

18-16-13W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - SHARON DRUG. CO. ET AL
Farm - Luerman No. 5

SEC. 18 T. 16 R. 13 W
CE $\frac{1}{2}$ SE SE

Total Depth. 3420' RDF
Comm. 6-22-46 Comp. 7-16-46
Shot or Treated. 500 gal. acid
Contractor.
Issued. 8-3-46

County. ☒ Barton
KANSAS



Elevation. 1950^{nh}

Production. Pump 2 BO & 2 BWP

CASING:
10 3/4" 160' Cem.
5 1/2" 3383' Cem.

Figures Indicate Bottom of Formations.

clay	0-20
post rock	40
shale w shells	565
shale & red rock	870
shale & shells	900
anhydrite	930
shale w shells	1675
shale	1685
lime	1860
shale w shells	1900
lime	1970
lime brkn	2055
shale & shells	2070
broken	2235
shale & shells	2445
lime brkn	2545
shale & shells	2785
lime	3092
lime brkn	3153
lime	3189
lime sft	3193
lime	3240
lime med	3242
lime sft	3254
lime	3390

T. D. w/rotary 3390=3388' RDF
lime 3420
Total Depth (cable) RDF

Tops:
Topeka 2834
Hoebner 3072
Base Oread 3102
Kansas City 3150
Arbuckle 3382

All measurement Rotary derrick floor