

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock,
Wichita, Kansas


17-32-2E

Company- ALADDIN PETROLEUM, CORP.
Farm- H. Miller "B" No. 1

SEC. 17 T. 32 R. 2E
NW SE SW

Total Depth. 3765'
Comm. 5-1-58 Comp. 5-30-58
Shot or Treated.
Contractor. Ark Valley Drlg. Co.
Issued. 8-16-58

County Sumner
KANSAS



CASING:
8 5/8" 200' w/150 sx cem.
5 1/2" 3691' w/125 sx cem.

Elevation. 1216' DF

Production. 20 BOPD & 144 BW

Figures indicate Bottom of Formations.

soil, shale	200
lime, shale	325
shale, shells	585
shale, red rock	780
shale, lime	815
shale, red rock	1115
lime, shale	1945
lime	2045
shale, lime	2360
sand	2512
shale, lime	2760
shale	2779
lime, Kansas City	2820
lime	2995
shale, lime	3104
lime	3119
lime, shale	3180
lime	3238
shale	3248
lime, shale	3350
Chat, Mississippi	3349-3369
lime	3380
lime, Mississippi	3403
lime	3608
shale, lime	3625
shale, Kinderhook	3651
shale, sand-Simpson	3670
sand, Simpson	3685
shale	3689
lime-Arbuckle	3706-3750
Total Depth	

TOPS: Geol.
Stalnaker (scout) 2358
Kansas City 2772
Mississippi conglomerate 3336
Mississippi chat 3342
Mississippi lime 3377
Kinderhook 3598
Simpson Section 3645
Arbuckle 3683