


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg, Wichita, Kansas.

CONTINENTAL OIL CO.
C. Stoskopf No. 2

SEC. 28 T. 16 R. 13 W.
NW¹/₄ SW
330' S. & 330' E of W¹/₄ cor.

Total Depth. 3370 (CFL 3369) P.B. 3335
Comm. 12-8-41 Comp. 12-24-41
Shot or Treated.
Contractor.
Issued. 3-14-42

County Barton.



CASING.

10 3/4" 407' cemented.
6" 3367' cemented.

Elevation

Production. Pot. 417B.

Figures Indicate Bottom of Formations. 9 EW Physical

shale and shells	802
red bed and shale	894
shale & lime shells	1188
shale	1683
shale and lime	2860
lime	2932
lime hard	2977
lime	3358
quartzite	3370
Total depth from cement floor level	3369

Top of Kansas City lime 3115
Top of Quartzite 3357

Plugged back T.D. 3335'

Ripped Casing in Kansas City lime
formation from 3129-3142. bailed
1/4 bbls of oil per hour.

1-2-42 500 gal acid.

1800' oil in hole, swabbed 62 bbls oil in
3 hours - 16 bbls off bottom last hour.

1-7-42 Established a 24 hour physical
Potential of 417 bbls oil 9 EW

Note - All of above footages are calculated from
cement floor level.