

*Plotted
Albert Wheeler*


WELL - VERNON O.G.
Ainsworth No. 3.

SEC. 33 T. 16 R. 13W
NW NE SE

Total Depth. **3386'**
Comm. 7-2-37 Comp. 8-3-37
Shot or Treated. 1000 Gals.
Contractor.
Issued. 8-21-37

County. Barton

AUG 21 1937



CASING:
10" 254'
6" 3375'

Elevation.

Production. Pot.1737 B.

Figures Indicate Bottom of Formations.

Shale & shells	100
shale	320
sand	360
gyp shells	650
red rock	751
GYP	840
shale	1550
brkn lime	1670
shale & shells	1735
shale	1845
shale & lime	2010
lime	2090
shale	2110
shale & lime	2182
sand	2190
shale & lime	2270
shale	2460
lime	2465
shale	2555
shale sdy lime	2665
shale	2765
brkn lime	2775
shale	2817
lime	3048
lime & shale	3085
sdv lime & shale	3105
shale	3140
shale & lime	3185
lime	3220
sdv lime sft	3240
lime	3350
lime & shale	3355
lime	3376
dolomite	3386
Total Depth.	

Top Siliceous 3376

2400' oil in 8 hrs.
1000 acid.
Pot.1737 B.