


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas

Company - BLACK-MARSHALL OIL CO.
Farm - Ainsworth No. 8.

SEC. 33 T. 16 R. 13 W
NWc NW

Total Depth. 3388'
Comm. 10-17-43 Comp. 10-28-43
Shot or Treated.
Contractor. Geo. H. Hannum
Issued. 4-8-44

County. Barton
KANSAS



CASING:
8 5/8" 195' Cem.
5 1/2" 3380' Cem.

Elevation. _____

Production. Temp. Phy. Pot. 182 B.

Figures Indicate Bottom of Formations.

| | |
|---------------------------|------|
| shale & shells | 720 |
| red rock | 865 |
| anhydrite | 900 |
| shale & shells | 1350 |
| salt | 1550 |
| shale & shells | 1750 |
| lime | 1970 |
| lime & shale brks | 2195 |
| shale & shells | 2775 |
| lime | 3100 |
| shale & shells | 3148 |
| lime K.C. | 3165 |
| cored 3160-65 | |
| lime Arbuckle | 3388 |
| Total Depth. (Rot. Meas.) | |

Tops (Derr. Fl. Meas.):
Lansing-K.C. 3148
Arbuckle 3383