

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - BLACK-MARSHALL OIL CO.
Farm - L. W. Ainsworth No. 10

SEC. 33 T. 16 R. 13 W
SEc SW

Total Depth. 3410'
Comm. 12-23-45 Comp. 1-15-46
Shot or Treated.
Contractor. Black-Marshall Oil Co.
Issued. 2-16-46

County. Barton

KANSAS



Elevation. 1955 ft

Production. Pot. 2620 B.

CASING:

8 5/8" 244' Cem.
5 1/2" 3406' Cem.

Figures Indicate Bottom of Formations.

surface clay	45
sand & gravel	130
shale blue, sand & gravel	225
shale	244
shale & shell	500
shale & red bed	810
anhydrite	850
shale & shell	1215
salt & shale	1410
shale & lime brkn	1690
lime brkn	1785
lime	1880
shale & lime	2195
shale	2690
shale & lime	2995
lime	3095
shale & lime	3190
lime K.C.	3218
lime	3340
lime & shale	3407
Arbuckle	3410
Total Depth.	

Tops:

Anhydrite	810
Lansing	3172
Arbuckle	3406