

KANSAS DRILLERS LOG


Ind

S. 33 T. 16 R. 13 ^E/_W

Loc. N2 N2 NE

County Barton

640 Acres.
N



Locate well correctly

Elev.: Gr. 1954

DF 1961 KB 1963

API No. 15 — 009 — 20,963
County Number

Operator
Sid Tomlinson

Address
Box 594 Twin Falls, Idaho 83301

Well No. #1 Lease Name Bradshaw

Footage Location
330 feet from (N) line 1320 feet from (E) line

Principal Contractor Thomas Drilling Co. Geologist J.E. Jespersen

Spud Date 12-2-75 Total Depth 3473' P.B.T.D. 3448'

Date Completed 1-30-76 Oil Purchaser Conoco

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	367	Regular	200	3% CaCl
Production	7 7/8	5 1/2	14	3472	Poz	125	18% salt 3/4% CFR-2
RECEIVED STATE CORPORATION COMMISSION							

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			4	Jets	3430-3434
TUBING RECORD					
Size	Setting depth	Packer set at			
2 1/2	3443	none			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
500 gals 15% NE acid	3430-3434
RECEIVED KANSAS GEOLOGICAL SURVEY WICHITA BRANCH	

INITIAL PRODUCTION

Date of first production <u>1-28-76</u>	Producing method (flowing, pumping, gas lift, etc.) <u>pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>52</u> bbls. Gas <u>0</u> MCF Water <u>0</u> bbls. Gas-oil ratio <u>0</u> CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) <u>Arbuckle 3430-3434</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Sid Tomlinson DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Oil

Well No. 1 Lease Name Bradshaw

S 33 T-16 R 13 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3425-36 (Arbuckle) 30/30/30/30 Recovered 60' gas in pipe 1247' gassy oil, no water. ISIP 911# FP 49# - 458# FSIP 863#				
Dresser Atlas ran Gamma Ray/Neutron/Laterlog.			Electric Log Tops:	
			Anhydrite	906 +1057
			Heebner	3100 -1137
			Brn. Lime	3182 -1219
			Lansing	3193 -1230
			Arbuckle	3428 -1465
			TD	3473 -1510

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1988

REGISTRATION DIVISION
MICHIGAN

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<u>Sid Tomlinson</u> Signature
	Operator
	Title
	1-30-76
	Date