

**KANSAS DRILLERS LOG**

S. 34 T. 16 R. 13 <sup>R</sup>/<sub>W</sub>

API No. 15 — 009 — 21,147  
County Number

Loc. C SE SE NW

County Barton

Operator  
Sid Tomlinson

Address  
Box 594 Twin Falls, Idaho 83301


Well No. #1 Lease Name Linsner

Footage Location  
330 feet from (N) (S) line 330 feet from (E) (W) line NW/4

Principal Contractor Revlin Drilling Geologist J. E. Jespersen

Spud Date 3-17-77 Total Depth 3707 P.B.T.D.

Date Completed 4-14-77 Oil Purchaser



Locate well correctly  
Elev.: Gr. 1929

DF \_\_\_\_\_ KB 1934

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	28	375	Poz.	235	3% CaCl
Disposal	7 7/8	5 1/2	14	3481	Poz.	125	18% Salt 3/4% CFR-2

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

(Fiberglas) **TUBING RECORD**

Size	Setting depth	Packer set at
2 7/8	3481	

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Sid Tomlinson		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Linsner	SWDW
S <u>34</u> T <u>16</u> R <u>13</u> <u>W</u>		

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
DST #1 3378-94 (Arbuckle) 30/30/30/30. Rec 30' oil & 240' muddy oil (77% oil, 23% mud) FP 82# -134# ISIP 650# FSIP 598#				
DST #2 3378-3402 (Arbuckle) 30/30/30/30 Rec 60' oil cut watery mud, 360' oil cut water, 300' sli oil cut water and 120' salt water. FP 41# - 392# ISIP 1072# FSIP 1072#				
Dresser Atlas ran Gamma Ray/Neutron/Laterlog				
<u>Electric Log Tops</u>				
			Anhydrite	856
			Heebner	3060
			Brn. Lm.	3145
			Lansing	3156
			Arbuckle	3388
			Reagan Sd.	3620
			Gr. Wash	3656
			TD	3707

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<p align="center"><i>Sid Tomlinson</i> Signature</p> <p align="center">OPERATOR Title</p> <p align="center">4-14-77 Date</p>
---------------	--