

State Geological Survey
WICHITA BRANCH

15-009-2111

KANSAS DRILLERS LOG

S. 34 T. 16 R. 13 ^E/_W
Loc. 100' E/C SW SW NE
County Barton

API No. 15 — 009 — 21,111
County Number

Operator
Sid Tomlinson

Address
Box 594 Twin Falls, Idaho 83301


Well No. #1 Lease Name Peschka

Footage Location
330 from S 430 from W of NE/Q
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Revlin Drilling Geologist J. E. Jespersen

Spud Date 12/10/76 Total Depth 3430 P.B.T.D. 3407

Date Completed 2/12/77 Oil Purchaser Phillips



Locate well correctly
Elev.: Gr. 1927
DF _____ KB 1933

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/2	8 5/8	28	365	common	250	2% gel 3% CaCl
Production	7 7/8	5 1/2	14	3427	Poz	125	18% salt 3/4% CFP-2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type jets	Depth interval
			4		3387-3390

Size	Setting depth	Packer set at
2 7/8	3402	none

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
250 gals 15% NE acid	3387-3390

INITIAL PRODUCTION

Date of first production <u>1/22/77</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>			
RATE OF PRODUCTION PER 24 HOURS	Oil <u>14</u> bbls.	Gas <u>0</u> MCF	Water <u>22</u> bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)		Producing interval(s) <u>3387-90 Arbuckle</u>		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Sid Tomlinson DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Peschka Oil

S34 T16 R13 E W

WELL LOG Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Table with 5 columns: FORMATION DESCRIPTION, CONTENTS, ETC., TOP, BOTTOM, NAME, DEPTH. Includes text: DST #1 3376-90 (Arbuckle) 30/30/30/30, Rec. 1250' clean oil, no water, FP 62-454 ISIP 969# FSIP 948#, Dresser/Atlas Ran Cased Hole Gamma Ray/Neutron, Anhydrite 847, Heebner 3057, Brn. Lm. 3145, Lansing 3158, Arbuckle 3387, TD 3430.

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received Signature: Sid Tomlinson OPERATOR Title: 3-17-77 Date