

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.

92 Jameson

STANOLIND OIL & GAS CO.
G.J. Niemann No. 7

SEC. 34 T. 16 R. 13W.
SE NW NW
1650' N of S.L. 990' E of WL

Total Depth. 3400

Comm. 9-17-37 Comp. 9-28-37


Shot or Treated. 2000 gal acid.

Contractor.

Issued. 12-11-37

Rotary and cable DEC 11 1937

County Barton.



CASING.

103/4" 242' 6" 3394' 9"

Elevation.

Production. Pot. 1620 B.
no wtr.

Figures Indicate Bottom of Formations.

clay yellow	40
sand	65
shale	250
sand	253
shale	302
sand	400
shale	450
sand	525
red bed	550
sdv shale	650
red bed	757
shale	853
anhydrite	898
shale	950
shale and lime	1330
salt shale and shells	1606
lime	1819
shale and shells	2072
broken lime	2185
sand	2196
lime and shale	2898
lime hard	3070
lime and shale	3088
lime	3110
shale	3163
lime	3205
shale	3250
lime	3390

Coring record Rotary cores.

1 3390-3400 7 1/10 Recovery.

broken lime 3391 1/2

shale grey and light grey 3394

dolomite grey very shaly 3394 1/2

dolomite very porous sat. 3397

dolomite shaley and green 3398

dolomite porous sat. 3400

Total Depth. Top siliceous 3394

siliceous lime 3394-3400

swabbed 12 bbls per hr before acidizing thro 6" casing.