

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas


35-16-13w

Company - SKELLY OIL CO.  
Farm - E. P. Gage No. 3

SEC. 35 T. 16 R. 13 W  
SE NE SW  
990' fNL 330' fE1 SW $\frac{1}{4}$

Total Depth. 3366  
Comm. 10-27-45 Comp. 11-15-45  
Shot or Treated.  
Contractor. Claude Wentworth Drlg. Co.  
issued. 1-19-46

County. Barton  
KANSAS



Elevation. \_\_\_\_\_

Production. Dry

CASING:

10 3/4" 797' Cem.  
5 1/2" 2513'

Figures Indicate Bottom of Formations.

sand & gyp	0-40
lime & shale	592
red bed, shale & shells	800
red bed & shale	817
anhydrite	835
shale	1365
shale & shells	1610
lime	1760
shale	1915
shale & shells	1984
lime brkn	2145
lime & shale	2455
shale & shells	2536
lime brkn	2630
lime & shale	2730
lime	3064
shale	3080
shale & lime	3168
lime	3189
lime sdy	3229
lime	3363
dolomite gy & brwn coarsely xlyn, sli. sat. & por.	3366
Total Depth.	

Tops:  
Anhydrite 817  
Lansing Lime 3117  
Arbuckle lime 3363

Sli. Por. & saturation 3363-66'