

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk Bldg. Wichita, Kansas


Company - TABLE MESA OIL CO.  
Farm - Ferrell No. 18

SEC. 28 T. 28 R. 8E  
NE NE NW

Total Depth. 2880'  
Comm. 4-2-48 Comp. 5-2-48  
Shot or Treated.  
Contractor. Rex & Morris Drlg. Co.  
Issued. 6-12-48

County. Butler

KANSAS



Elevation. \_\_\_\_\_

Production. Dry

CASING:  
13-3/8" 727' Pulled  
10" 1390' Pulled  
8" 1950' Pulled  
7" 2353' Pulled

Figures Indicate Bottom of Formations.

cellar	7	shale	1055	Caving 2740 to 2743'
lime	20	lime	1063	shale & chat 2830
shale	35	shale	1072	lime 2880
red rock	45	lime	1085	5 1/2 BWPB 2870-80'
shale	75	shale	1095	Total Depth 2880
lime	100	lime	1115	
shale	145	shale	1155	
lime	170	lime	1170	
shale	185	shale	1210	
red rock	195	Hole caving 1170'		
lime	210	lime sdy	1220	
shale & lime	240	shale	1245	
red rock	245	lime	1300	
lime	265	caving 1230-60'		
shale	280	1/2 BWPB 1260-65'		
lime	310	shale	1320	
shale	320	lime	1355	
lime	325	shale	1385	
shale & shells	345	lime	1390	
shale	380	shale	1410	
lime	390	sand	1430	
shale & shells	425	7 BWPB 1410-20'		
shale	445	shale	1605	
lime	450	shale sdy	1620	
shale	465	shale	1625	
lime	470	lime	1660	
shale	500	show oil 1630'		
shale sdy	510	HF" 1630-40'		
little wtr & puff gas at 500'		sand sharp	1670	
shale	585	sand	1685	
lime	595	lime	1705	
shale	625	lime sdy	1745	
lime	630	lime	1875	
shale	645	sand	1910	
lime	665	lime	1960	
shale	675	shale	1990	
redurce hole 675		lime	1995	
lime	690	shale	2010	
lime hrd	720	lime	2170	
3 BWPB 695-705		3 BWPB 2070-2085'		
shale	768	shale blk	2172	
lime	773	lime	2215	
shale	800	shale	2295	
lime	810	lime	2305	
shale	815	shale	2345	
lime	825	lime	2353	
shale	845	hole caving 2320-50'		
lime	850	shale	2370	
shale	855	lime	2400	
lime	865	shale & shells	2420	
shale	935	lime	2500	
lime brkn	950	shale	2580	
lime	975	lime	2585	
shale & lime	985	shale	2672	
lime	1010	red rock	2680	
shale	1020	shale	2687	
lime	1035	lime	2697	
		shale	2805	