

State Geological Survey
WICHITA, BRANCH

KANSAS DRILLERS LOG

IMPORTANT
Kans. Geo. Survey request
samples on this well.

15-009-21555

API No. 15 — 009 — 21,555
County Number

Operator

Wayne Stoskopf

Address

R. R. #2 Hoisington, Kansas 67544

Well No.

#4

Lease Name

Rexroat

Footage Location

feet from (N) (S) line 990

feet from (E) (W) line 330

Principal Contractor

LD Drilling Co

Geologist

James C. Musgrove

Spud Date

1-19-79

Total Depth

3350 1/2

P.B.T.D.

Date Completed

1 25 79

Oil Purchaser


Continental

S. 35 T. 16 R. 13 E W

Loc. NW SW SW

County Barton

640 Acres
N



Locate well correctly

Elev.: Gr. 1886

DF 1888 KB 1891

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12	8 5/8		211	83 SK Portland	82	Poz mix
Production	7	5 1/2	15 1/2	3347 1/2	75 " "	1550	" "

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production 2-19-79		Producing method (flowing, pumping, gas lift, etc.) Pumping		
RATE OF PRODUCTION PER 24 HOURS	Oil 40 bbls.	Gas	Water no water	Gas-oil ratio
Disposition of gas (vented, used on lease or sold)			CFPR	
			Producing interval (s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
WAYNE STOSKOFFDESIGNATE TYPE OF COMP.: ☒ OIL GAS,
DRY HOLE, SWDW, ETC.:Well No.
4Lease Name
REXROATS T R E
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
ANHYDRITE	794		+1097	
HOWARD	2688		- 797	
SEVERY	2707		- 916	
TOPEKA	2728		- 937	
HEEBNER	3012		- 1121	
TORONTO	3030		- 1139	
DOUBLAS	3042		- 1151	
BROWN LIMITE	3098		- 1207	
LANSING	3112		- 1221	
BASE KANSAS CITY	3325		- 1434	
ARBuckle	3344		- 1453	
" " TD	3350 1/2		- 1459 1/2	
DST NO 1 3335 1/2 - 3350 1/2				
Open I.F. 45" FF 45"				
BLow weak increasing to				
Strong I.F.P. Strong FFP				
Recovery 480' clean sandy oil				
120 muddr " "				
60 Frothy muddr "				
660				
Pressures 1st P, 988 PSI (30")				
FSIP 956 PSI (30")				
FFP 208-260 PSI				
HSH 1900-1817 PSI				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Wayne Stoskoff

Signature

operator

Title

2-20-79

Date