

KANSAS WELL LOG BUREAU--- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

23-32-2E ✓


COMPANY **LARIO OIL & GAS COMPANY**

FARM **Wenrich** NO. **19**

SEC. **23** T. **32** R. **2E**
 LOC. **NE NE SW NW**
220° S & 220° W Cen. NW/4

TOTAL DEPTH **2060**
 COMM. **7-6-48** COMP. **7-22-48**
 SHOT OR TREATED
 CONTRACTOR
 ISSUED **11-11-50**

COUNTY **Sumner**



CASING

8 5/8" 210' cem. w/125 sx
5 1/2" 2007' cem. w/100 sx

ELEVATION

PRODUCTION **55 bbls. oil /**
6 water

FIGURES INDICATE BOTTOM OF FORMATIONS

shale, sand & lime	111
lime & shale	220
lime, shale & sand	395
lime	435
redbed	455
lime & shale	590
redrock	595
lime & shale	625
lime & shale	672
shale	1105
lime & shale	1125
lime	1178
lime & shale	1230
sandy lime	1235
lime & shale	1725
lime	1915
lime & shale	1980
sandy shale	2052
sand	2060
Total Depth	"

Rotary total depth 2021'

Tops:
 Stalnaker 2007

Perf: 109/ 2008-2021
 50/ 2025-35
 30/ 2050-55

Shot: 45 qts. Nitro.