

23-32-2E


Company - SLOCUM & JARVIS
 Farm - Wenrih. No. 2 -A

SEC. 23 T. 32 R. 2E
 SW NW SW

Total Depth. 2126'
 Comm. 8-9-48 Comp. 8-20-48
 Shot or Treated.
 Contractor. Watson Drilling
 Issued. 12-4-48

County. Sumner

KANSAS



5 1/2" CASING:
 2122 cement w/75sx

Elevation. 1192 *ft.*

Production. 100 bbl

Figures Indicate Bottom of Formations.

shale shells	200
lime shale	835
shale shells	1168
lime shale	1935
shale sand	1945
shale lime	1958
shale shells	2045
lime shale	2053
shale sdy lime	2126
total depth	

Core 1168-85, full rec. 17'.

shale	1168-73
lime	1175 $\frac{1}{2}$
shale	1176 $\frac{1}{2}$
shale	1180 $\frac{1}{2}$
lime, slyn	1185
lime,	1930

partly oil stained

lime brown, No Show 1935

sand, fair oil SAT. 1940

Core, rec. 13' 1940-58

sand, fair oil Sat. 1944 $\frac{1}{2}$

shale dk, 1949

shale liney 1953

saturated sand zone 1935-44 $\frac{1}{2}$

lime 2052

sand and shale 2082

sand Fair Sat. 2084

sand and shale 2094

No oil show

shale 2104

shale and sand 2110

fair oil odor

shale and sand 2122

no show oil