

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
 508 East Murdock, Wichita, Kansas


1-16-140

Company- HELMERICH & PAYNE, INC.  
 Farm- Stottinger No. 8

SEC. 1 T. 16 R. 14W  
 CW/2 W/2 NE

Total Depth. 3451  
 Comm. 3-3-51 Comp. 3-13-51  
 Shot or Tested.  
 Contractor. Pool Brothers, Inc.  
 Issued. 5-24-52

County Barton  
 KANSAS



Elevation. 1883 ft.

Production. Pmp. & BO NET

CASING:  
 8 5/8" 632'  
 5 1/2" 3098 1/2'

Figures indicate Bottom of Formations.

rock & clay	40
sand & shale	70
shale & shells	386
iron & shale	400
sand & shale	585
shale & red bed	632
anhydrite	894
shale & shells	1240
salt & shale	1350
shale & shells w/lime	
streaks	1670
shale & lime	1740
sandy shale	1850
lime	1970
lime & shale	2575
lime	3102
lime	3149
lime & shale	3160
lime	3451
Total depth	

Scout Tops:  
 Heebner 3009  
 Kansas City 3076

On Kansas State Corporation  
 Docket No. 45, 298-C (C-2887)  
 this well was converted into a  
 Salt Water Disposal Well. Same  
 was deepened as follows:  
 4 1/2" OD Liner was set at (Top  
 3058' in 5 1/2" casing) (Bottom  
 at 3370') 312' total. cem. w/35  
 sx of cement.