

Plotted

1-16-149 E. J.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bank Bldg, Wichita, Kansas.


SHELL PETROLEUM CORP.
Schneider No. 8-B.

SEC. 1 T. 16 R. 14W.
SE NW NW
990' NL 979' WL.

Total Depth. 3312.
Comm. 9-25-38 Comp. 10-22-38
Shot or Treated. 2000 and 4000 gal acid.
Contractor. Crow Drilling Co.
Issued. 11-26-38

County Barton.

NOV 26 1938



CASING.

103/4" 650'
7" 3289'

Elevation.

Production. Pot. 2176 B.
No wtr.

Figures Indicate Bottom of Formations.

surface clay	35
shale and shells	345
iron and shalo	510
red rock & shale	652
red bed	852
anhydrite	877
shale and shells	1227
salt and shale	1252
shale and salt	1547
shale and lime	1649
shale and anhydrite	1770
shale and lime	1908
lime	1925
shale and shells	2008
shale and lime	2296
shale and lime strks	2423
shale and lime	2584
shale and lime strks	2680
shale	2690
lime and shale strks	2754
shale and lime strks	2765
lime	2826
lime	3285
dolomite	3312
Total Depth.	

Core No. 4	3290-3302
	light oil stain.
Core No. 5	3302-3306
	fair porosity and streaks of fair oil stain.
	2100' oil 3306.
Core No. 6	3306-07
	2300' oil
	2000 acid.
Core No. 7	3307-10
	3025' oil
Core No. 8	3310-12
	3025' oil.
	Acid 4000 gal.

light oil stain 2940-48
light oil stain 3086-98
Good porosity no oil stain 3154-72
Good porosity good oil stain 3280-84
light oil stain 3287

Core No. 1 3287-90
light oil stain.
3290 equals 3290 S.L.M.
Core No. 2 3292-94
Good oil stain 550' fluid
Core No. 3 3294-98